MRS. D. BANERJEE
PRINCIPAL

EMAIL – DAVKOYLANAGAR@GMAIL.COM
WEB SITE - WWW.DAVKOYLANAGAR.COM
☎ : 0326 -- 2230715
FAX : 0326 – 2230715
MOB. NO. – 9905521779

D.A.V. PUBLIC SCHOOL , KOYLA NAGAR

BCCL TOWNSHIP, KOYLANGAR, DHANBAD- 826005

SCHOOL NO.:66202 AFFN NO. 3430148,

Ref. No. DAVKN/Tender/2026-27/898 . Date: 20-11-2026

Notice for inviting Tender/Quotations for change of window glasses, repairing of window frames, change/new Handles and New window panes (Almunium channel with visible transparent glass)

Sealed quotations/Tenders from reputed and experienced Civil Contractors with good Credential are invited by the undersigned on behalf DAV Public School , BCCL Township, Koylanagar, Dhanbad (JH) **for change of window glasses, repairing of window frames, change/new Handles and New window panes (Almunium channel with visible transparent glass) . Please visit the school under intimation to the undersigned for details of numbers, measurements and factual position of the work.**

Please go through the following Points /Terms & conditions before submitting the Tender/Quotations.

- **Date for submitting the Quotations/Tenders – w.e.f. 21-11-2026 9.30 a.m. to 27-11-2026, 2.30 p.m.**
- **Sealed Tender/Quotations are to be submitted by hand /through authorized person in the office of the undersigned as per date and time mentioned above.**
- **Registration and Licences: Must having the valid registration and relevant Licennces for the work cartegory.**
- **The company/Contractor must have a valid GSTIN and PAN Number and to be mentioned in the quotation/Tender.**
- **Experience: The Contractor must have an experience for at least three years in the field.**
- **Financial ability: The contractor must have financial ability to complete the work as per schedule without any Advance for the same.**
- **No any alteration to be allowed without permission in the existing pattern.**
- **The Payment will be made after a maximum time of 30 days after completing the work verified and satisfied by the School's Architect as per parameter fixed by them.**
- **TDS will be deducted as per norms.**
- **The Work(s) will be awarded to the lowest bidder only in full rate/total value and complete the all parameters as per schedule. No part work will be awarded in any condition.**
- **The work order may be cancelled by the Authority if the work is not accepted and started within one week from the date of issue.**
- **No payment will be done if the work is not completed within 30 days from the day of starting/ workorder given by the school.**
- **School's Building-sub-Committee will supervise the quality of the materials.**

Schedule is attached herewith. Quotation is to submitted as per schedule alongwith total number of each items (after duly counted) . Payment will be made after verification of total numbers of each items on actual basis.

P-1/2

(D. C. Banerjee)
Principal

PRINCIPAL
D.A.V. PUBLIC SCHOOL
KOYLA NAGAR DHANBAD

MRS. D. BANERJEE
PRINCIPAL

EMAIL – DAVKOYLANAGAR@GMAIL.COM
WEB SITE - WWW.DAVKOYLANAGAR.COM
: 0326 -- 2230715
FAX : 0326 – 2230715
MOB. NO. – 9905521779

D.A.V. PUBLIC SCHOOL , KOYLA NAGAR

BCCL TOWNSHIP, KOYLANGAR, DHANBAD- 826005

SCHOOL NO.:66202 AFFN NO. 3430148,

20/11/2026

Schedule/Desire requirement /quality of the materials

1.. Glass quality – 04 (four) mm thickness pin head/stripe window glass to be fixed with almunium L channel with screw or pins. Fitting with putti is not allowed.

Rate to be quoted per square feet including all labour/fitting charges and materials . (Physical verification and counting is must before quoting the rate)

2.. Handles – steel /good quality GI made handle as per existing pattern.

Rate to be quoted per piece for new handles and per piece for fixing of screw/welding work for reparing of old handles –separately.

. (Physical verification and counting is must before quoting the rate)

3.. Repairing of window frames/grills – As per actual Number with proper fabrication work and civil work as per need.

Rate to be quoted per window as per actual number - (Physical verification and counting is must before quoting the rate)

4.. Replacement of exsiting iron made frame by good quality (TATA or equavalant) Almunium channel/window frame – **(As per need if old frame is not repairable) . Good quality/heavy 12 guage and 2.5 x 01 inch inch wide dual channel almunium frame with transparent 05 mm premium quality Glass .**

Rate to be quoted per square feet alongwith frame and glass and fitting charges /all charges inclusive . Sample of window glasses , handle and almunium channel to submitted alongwith the quotations in separate packet with name of the contractor.

. (Physical verification and counting is must before quoting the rate)

Please visit the school under intimation to the undersigned for details of numbers, measurements and factual position of the work before submiting the quotation.

(D. C. Banerjee)
Principal

PRINCIPAL
D.A.V. PUBLIC SCHOOL
KOYLA NAGAR DHANBAD

P-2/2